


TAX MAP
NOT TO SCALE

ZONING MAP
NOT TO SCALE

Plant Key

- Deciduous Tree
- Flowering Tree
- Evergreen Tree
- Large Decid. Shrub
- Med. Decid. Shrub
- Ground Cover Shrub
- Evergreen Shrub



R-2 ZONING DISTRICT SCHEDULE
(EXPANDED C-2 ZONE ORD 141-72D)

ITEM	REQUIRED	EXISTING	PROPOSED	ORDINANCE
LOT REQUIREMENTS				
MIN. LOT AREA (SF)	6,000	33,250 (0.763 Ac)	33,250 (0.763 Ac)	\$141-77.C(1)
MIN. LOT WIDTH (FT)	60	245	245	\$141-77.C(1)
BUILDING SETBACKS & HEIGHT:				
MIN. FRONT YARD (FT)	30	66.1	66.1	\$141-77.C(2)
MIN. SIDE YARD (FT)	8	6.2*	6.2*	\$141-77.C(3)(b)
MIN. SIDE YARD-STREET (FT)	25	9.5*	9.5*	\$141-77.C(3)(b)
MIN. REAR YARD (FT)	35	N/A	N/A	\$141-77.C(4)
MAX. BLDG HEIGHT (FT)	35/2.5 STORIES	<35	<35	\$141-77.B
MAX. BUILDING COVERAGE (%)	30	49*	49*	\$141-77.C(5)(a)
MAX. LOT COVERAGE (%)	65	51	64	\$141-77.C(5)(b)

* DENOTES EXISTING NON-COMFORMANCE

C-2 ZONING DISTRICT SCHEDULE
(EXPANDED C-2 ZONE ORD 141-72D)

ITEM	REQUIRED	EXISTING	PROPOSED	ORDINANCE
LOT REQUIREMENTS				
MIN. LOT AREA (SF)	5,000	35,535.6 (0.815 Ac)	35,535.6 (0.815 Ac)	\$141-81.C(1)
MIN. LOT WIDTH (FT)	50	218.5	218.5	\$141-81.C(1)
BUILDING SETBACKS & HEIGHT:				
MIN. FRONT YARD (FT)	40	42.1	42.1	\$141-81.C(2)(a)
MIN. SIDE YARD (FT)	10	5.9*	5.9*	\$141-81.C(2)(b)(3)
MIN. REAR YARD (FT)	35	N/A	N/A	\$141-81.C(2)(c)
MAX. BLDG HEIGHT (FT)	35	<35	<35	\$141-81.B
MAX. BUILDING COVERAGE (%)	50	29	29	\$141-81.C(3)(a)
MAX. LOT COVERAGE (%)	85	88	87	\$141-81.C(3)(b)
MIN. RESIDENTIAL BUFFER (FT)	6	0	6	\$141-82.H(2)(c)

* DENOTES EXISTING NON-COMFORMANCE

PARKING REQUIREMENTS

ITEM	REQUIRED	PROPOSED	ORDINANCE
PARKING			
MIN. STANDARD SPACE SIZE (FT)	10 x 20	9 x 18**	\$141-73 (DEF)
MIN. NUMBER OF SPACES FOR RETAIL (ASSUMING 3 RETAIL USES)	1 PER 200 SF OF SALES AREA	3,600 SF (18 REQ'D)	\$141-87.A(2)(f)(2)(b)
MIN. NUMBER OF SPACES FOR 24 SEAT RESTAURANT WITH 3 EMPLOYEES	9	9	\$141-87.A(2)(f)(2)(b)
MIN. NUMBER OF SPACES FOR WAREHOUSE	1 PER EMPLOYEE	6 EMPLOYEES	\$141-87.A(2)(m)
TOTAL NUMBER OF SPACES	30 (1)	30	\$141-87.A(2)(f)(1)

** DENOTES PROPOSED NON-COMFORMANCE
(1) MAX NUMBER OF REQUIRED PARKING SPACES ASSUMES BOTH TENANT SPACES OCCUPIED BY 24 SEAT CAFE/RESTAURANT TYPE USES WHICH GENERATES GREATER PARKING DEMAND THAN RETAIL USES OF THE SAME SIZE

GENERAL NOTES

- OWNER/APPLICANT: PHILIP 5115 LLC, 1387 BROOKSTONE DRIVE, GARNETT VALLEY, PA 19060
- EXISTING CONDITIONS TAKEN FROM A PLAN ENTITLED "PLAN OF TOPOGRAPHIC SURVEY, #5115 ROUTE 38, TOWNSHIP OF PENNSAUKEN, COUNTY OF CAMDEN, NEW JERSEY", BY PENNELL LAND SURVEYING, INC., DATED MARCH 16, 2020.
- APPLICANT SEEKS USE VARIANCE APPROVAL SO AS TO PERMIT CONTINUED USE OF AN EXISTING WAREHOUSE/RETAIL OPERATION ON THE SUBJECT PROPERTY WITH THE ADDITION OF TWO 1,200 SF TENANT SPACES FOR NEW RETAIL OR RESTAURANT USES.
- NO FRESHWATER WETLANDS EXIST ON THIS SITE, AS REFERENCED FROM NJDEP GEOWEB MAP VIEWER.
- THE PROPERTY DOES NOT FALL WITHIN A FLOOD PLAIN ZONE ACCORDING TO THE MOST RECENT FEMA FIRM MAP 3407C003F.
- THERE ARE CURRENTLY NO KNOWN DEED RESTRICTIONS OR COVENANTS ASSOCIATED WITH THE SUBJECT PROPERTY.

WAIVERS & VARIANCES

- VARIANCES ARE REQUESTED FROM THE FOLLOWING:
 - SECTION 141-73 - MINIMUM PARKING SPACE SIZE: 10' X 20' REQUIRED; 9' X 18' PROPOSED
 - SECTION 141-77.A - TO ALLOW THE CONTINUE USE OF WAREHOUSE FACILITY IN THE R-2 RESIDENTIAL ZONE
 - SECTION 141-77.C(3)(b) - MINIMUM SIDE YARD: 25 FEET TO A STREET REQUIRED; 6.2 FEET EXISTING; 8 FEET TO A SIDE YARD REQUIRED; 6.2 FEET EXISTING
 - SECTION 141-77.C(5)(a) - MAXIMUM BUILDING COVERAGE R-2 RESIDENTIAL ZONE: 30% PERMITTED; 49% EXISTING
 - SECTION 141-81.C(2)(b)(3) - MINIMUM SIDE YARD: 10 FEET REQUIRED; 5.9 FEET EXISTING

THE PETTIT GROUP, LLC
Engineering • Architecture • Planning
497 Center Street • Sewell, NJ 08080
Tel: 856-464-9600 Fax: 856-464-9606
www.pettitgroup.com
Certificate of Authorization No. 246A28131400

REVISIONS

NO.	DESCRIPTION	DATE
1	PER BOARD REVIEW	08/20/20

FOR APPROVAL PURPOSES ONLY

ALL DOCUMENTS PREPARED BY THE PETTIT GROUP, LLC ARE INSTRUMENTS OF SERVICE IN RESPECT TO THE PROJECT. THEY ARE NOT INTENDED OR REPRESENTED TO BE SUITABLE FOR REUSE BY OWNER OR OTHERS ON EXTENSIONS OF THE PROJECT OR ANY OTHER PROJECT ANY REUSE WITHOUT WRITTEN PERMISSION BY THE PETTIT GROUP, LLC. FOR THE SPECIFIC PURPOSES INTENDED WILL BE AT THE OWNER'S SOLE RISK, AND WITHOUT LIABILITY OR LEGAL EXPOSURE TO THE PETTIT GROUP, LLC AND OWNER SHALL INDEMNIFY AND HOLD HARMLESS THE PETTIT GROUP, LLC FROM CLAIMS, DAMAGES, LOSSES AND EXPENSES ARISING OUT OF OR RESULTING THEREFROM.

DESIGNED BY: BWC	JOB NO: 1640-01
DRAWN BY: BWC	DATE: 05/28/20
CHECKED BY: BWC	SCALE: 1" = 20'

USE VARIANCE PLAN


5115 ROUTE 38
BLOCK 6001, LOT 55, PLATE 60
PENNSAUKEN TOWNSHIP
CAMDEN COUNTY
NEW JERSEY

FOR
PHILIP 5115 LLC
1387 BROOKSTONE DRIVE
GARNETT VALLEY, PA 19060

BRIAN W. CLEARY, PE
Professional Engineer
State of New Jersey • License # GE 51748
State of Pennsylvania • License # PE081074
State of Maryland • License # 54411

USE VARIANCE PLAN

SHEET NUMBER:
1 of 1



P:\1640\1640-01\Pennsaiken-Use-Variance-Plan.dwg (Sheet 01) - User: Brian W. Cleary, 05/28/2020 1:57 PM, AutoCAD